

file
Buss Shutter

Estimate of

Cost.

Buss Shutter

15 Peg 4 x 4 x 5-0

1 " 4 x 6 x 5-0

2 " 4 x 4 x 6-0

2 " 4 x 4 x 7-0

1 " 4 x 4 x 7-0

2 " 2 x 4 x 6-6

1 " 2 x 4 x 6-0

3 " 2 x 4 x 5-0

6 " 2 x 4 x 9-0

5-0 ft of Sheathing

1/2 sq of Roof

120 ft of Roofing

1 Ridge Roll 6-0

20 lbs of Nails

1 gal of Paint

2 Locust Post

used in lieu of Pine Slabs:
 to be applied vertical
 12' x 1" Rough Boards with 3" x 1" Battens, or
 T & G Boards
 to be applied horizontal
 Shiplap or Beveled Siding.
 Note:
 If T & G, Shiplap, or Beveled Siding
 are used apply 2 Coats Standard House
 Paint to Interior and Exterior. Color to be
 Amber-Orange.

Roofers = $3\frac{1}{4}$ cents } 320 sq ft = \$10.40
 2 X 4's = $3\frac{1}{4}$

Sheathing $3\frac{1}{4}$ } 80 sq ft
 Ch. Gr. 28 gauge $5\frac{1}{2}$ } 6 ft
 Ridge Roll 12 cts per foot

4 posts at 25 cts
 Paint 2 coats with spray 1 gal.
 under roof 1/2 gal.
 Labor

4.40
 .72
 1.00
 16.52
 3.00
 1.00

\$20.52
 10.26 → \$30.78

8.00
 2.00
 8.00
 22.00

SCHOOL BUS WAITING STATION

PLAN No. WS-1	DIVISION OF SCHOOL BUILDINGS STATE DEPARTMENT OF EDUCATION RICHMOND VIRGINIA	Nov. 1936
------------------	--	--------------